

~~SURVEY~~
~~MONUMENT~~

MAR 31 1994

~~CONFIDENTIAL~~

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED

1993 DEC 29 AM 10:33

For corners in
WEXFORD
(County)

Located In:	Corner Code #:
T <u>21N</u> R <u>10W</u>	<u>L-13</u>
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

Linda Loughmiller
WEXFORD COUNTY, MI
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, CRAIG J. PULLEN, in a field survey on DECEMBER 16, 1993

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-13 1837 GLO SURVEY BY J. BRINK, WOOD POST W. PINE 12" S48°E 8 LKS Y. PINE 11" N65°W 12 LKS
 1963 C. ROSER, PS #12028 SURVEY FOR MSHD, CORNER RECORDED IN L.2, P.867 SET 1" PIPE BY SINGLE PROPORTION 16" TW. RED PINE N20°W 41.52' 20" R. PINE N30°E 68.07' 7" W. PINE N50°W 47.59' NE COR., SEC.2, T20N, R10W N89°39'36"E 341.19'
 1991 C. ROSER SURVEY, CORNER RECORDED IN L.4, P.99 FOUND 1" PIPE FROM 1963 MSHD SURVEY; ADDED DNR CAP AND SET CEDAR POST.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-13 FOUND DNR CAP ON 1" PIPE AND WITNESSES FROM L.4, P.99 INTACT. THIS CORNER IS ACCEPTED AS A FAITHFUL AND CAREFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Peer Group Reviewed and Approved
Date: December 28, 1993
Richard D. Wilcox
Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13 S¼ CORNER, SEC.36, T21N, R10W
 DNR CAP ON 1" PIPE AND CEDAR POST
 24" RED PINE N28°E 68.07' (1963 WIT.)
 18" TWIN RED PINE N22°W 41.31' (1963 WIT.)
 16" MAPLE S48°E 7.45'
 16" RED PINE N65°E 16.83' (1991 WIT.)
 NE CORNER, SEC.2, T20N, R10W N89°40'E 341.40'



Signed by Craig J. Pullen Date DECEMBER 23, 1993

Surveyor's Michigan License No. 39095