

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Wexford Located In: _____ Corner Code # _____
 (County)

- | | | | | | |
|--------------------------------------|---|------------|---|------------|------------|
| 1. Public Land Survey | T | <u>21N</u> | R | <u>10W</u> | <u>M-5</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous Property in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |

RECEIVED

1996 DEC 13 PM 3:33

Linda Loughmiller
 WEXFORD COUNTY, MI
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, George D. Smith, in a field survey on August 13, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-5) 1837 GLO Quarter Section Post by John Brink, Deputy Surveyor, Beech 10 S 62° W 22, Beech 10 N 45° W 29
 1884 A. J. Teed Survey Liber 1, Page 74, set stake from station trees, witnesses (FB66, Pg. 59) W. Pine 24 N 56° E 84, W. Pine 24 S 42° E 38
 1896 A.J. Teed Survey, Liber 1, Page 30, found stake ok no witnesses given
 1906 D.E. Teed Survey, Liber 1, Page 75 found stake no description given W. Pine 16 N 6° W 52 links
 1972 WCRC found 3/8" rod 8" deep 4" pine S 45° E 127.50', 12" Cherry S 30° W 103.00' WCRC old witness book 30" pine N 67° E 45.00' Pine stump S 70° W 52.00
 1979 Wilcox Survey by J. L. Wilcox RLS#14102, LCRC, Liber 03, Page 207 found 5/8" re-rod in line with fence North added Wex. Co. Mon., North 3288 gate post S 45° E 50.45' Fence Post S 50° W 45.59 P.P. West 33.07 corner fence post (old MSHD nail).
 1990 J. Ray RLS #25869, Certificate of Survey, Liber 69, Page 832, found Wex. Co. Mon. North corner fence post 32.75', S 55° W P. Pole 45.70', S 60° E corner fence post 51.30, West guy pole 33.45.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-5) Found Wexford County Mon. with Aluminum cap +/- Centerline Road South-East and 2' Southerly of fence line to West. This corner position matches GLO Swamp call to North within 10' and A.J. Teeds 1896 distance to the East 1/4 within 4'. This corner is accepted as the best available evidence of the position of the original corner, being the section corner common to Sections 12 and 13, T21N, R10W and Sections 7 and 8, T21N, R9W

SURVEY &
 REMONUMENTATION
 MAY 26 1987
 COMMISSION

Peer Group Reviewed and Approved
 Date: 14 Nov 96
Richard D. Wilcox
 Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-5) Wexford Co. Mon with Aluminum Cap
 S52°W - 45.65' - Power Pole
 N82°E - 33.41' - Power Pole
 S44°E - 51.35' - Corner fence post
 N55°E - 58.48' - Centerline of 2" Steel post 1.5' above ground



Signed by George D. Smith Date 11-21-96
 Surveyor's Michigan License No. #39098