

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in <u>Wexford</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>21N</u> R <u>10W</u>	<u>M-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED
 1996 DEC 13 PM 3: 33
Linda Loughmiller
 WEXFORD COUNTY, MI
 REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, George D. Smith, in a field survey on August 13, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-6) 1837 GLO Quarter Section Post by John Brink, Deputy Surveyor, Beech 8 N 20° W 21, Beech 10 S 84° W 50
- 1883 A. J. Teed Survey Liber 1, Page 29, (FB68, Pg. 83) Corner found W. Pine 24 S 53° E 35
- 1896 A.J. Teed Survey, Liber 1, Page 30, corner found no description given, W. Pine 20 S 54 1/2° W 65, W. Pine 16 N 67° E 33
- 1906 D.E. Teed Survey, Liber 1, Page 75 found no description given W. Pine 18 S 80 1/2° E 16
- 1973 J. Granger R.L.S. #16041 LCRC Liber 2, Page 610 found 1/2" pipe pinched together corner fence post S 89°30' E 29.88' 6" W. Pine S 46° E 62.06' 8" W. Pine N 74° 30' W 39.43'
- 1990 J. Ray RLS #25869, Certificate of Survey, Liber 69, Page 832, found 1/2" pipe in rocks East fence post 30.35', West corner fence post 33.07, N 70° W 16" W. Pine 39.42' N 30° W 10" Oak 61.30'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-6) Found 1 1/4" Pipe surrounded by stones and the remains of 1 of Teeds 1896 White Pine Witness trees. This corner is accepted as the best available evidence of the position of the original corner, being the 1/4 corner common to sections 13 and 24, T21N, R10W and Sections 18 and 19, T21N, R9W

SURVEY &
 REMONUMENTATION
 MAY 20 1997
 COMMISSION

Peer Group Reviewed and Approved
 Date: 14 Nov 96
Richard D. Wilcox
 Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-6) Drove 5/8 x 36" Iron 5/8" x 36" Iron with Wexford Co. brass cap stamped E 1/4 13, 1996, PS#39098 in existing 1 1/4" pipe

- N75°W - 39.38' - 24" W. Pine
- S35°E - 50.53' - P. Pole
- N48°E - 60.50' - Base of 2" Diameter flag pole
- N18°W - 61.19' - TW 10" Oak
- S42 1/2°W - 65 links - 20" W. Pine (1896 A.J. Teed) S 40°W 43.1± M. W.Pine Stump Remains



Signed by George D. Smith
 Surveyor's Michigan License No. # 39098

Date 11-21-96

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983