

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in Wexford Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

- |                                      |   |            |   |            |            |
|--------------------------------------|---|------------|---|------------|------------|
| 1. Public Land Survey                | T | <u>21N</u> | R | <u>10W</u> | <u>M-8</u> |
|                                      | T | _____      | R | _____      | _____      |
|                                      | T | _____      | R | _____      | _____      |
|                                      | T | _____      | R | _____      | _____      |
| 2. Property Controlling in Section   | S | _____      | T | _____      | R          |
|                                      | S | _____      | T | _____      | R          |
| 3. Miscellaneous Property in Section | S | _____      | T | _____      | R          |
|                                      | S | _____      | T | _____      | R          |
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

**RECEIVED**  
 1996 DEC 13 PM 3:34  
*Linda Loughmiller*  
 WEXFORD COUNTY, MI  
 REGISTER OF DEEDS  
 Register of Deeds Stamp & File Number

I, George D. Smith, in a field survey on August 13, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		28		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- M-8) 1837 GLO Quarter Section Post by John Brink, Deputy Surveyor, Hemlock 7 S 41 1/2° W 32, Beech 8 N 7° W 14
- 1891 A.J. Teed Survey, Liber 1, Page 32, Corner found no description given, Pine 30 S 32 1/2° W 39
- 1898 D.E. Teed Survey, Liber 1, Page 85, large stake in side of road, surrounded with stones, Pine 30 S 32 1/2° W 39L, Pine 30 N 40° E 52 (FB 86, Page 40)
- 1969 WCRC mon. box no witnesses given
- 1980 Granger Engineering, Certificate of Survey by J. Ray RLS #25869, Liber 1, Page 814 found mon. box with 3/4" iron, corner fence post East 39.00', 6" Pine N 30° W 67.83', P. Pole S 76° W 79.13', 10" Pine S 52° W 75.46'

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- M-8) Found 5/8" Iron in Mon. Box at Intersection of Roads North-South and West and in line with fence to East. This corner is accepted as the best available evidence of the position of the original corner, being the 1/4 corner common to Section 24, T21N, R10W and Section 19, T21N, R9W

Peer Group Reviewed and Approved  
 Date: 14 Nov 96  
*Richard D. Wilcox*  
 Richard D. Wilcox, Wexford County Surveyor

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- M-8) Set Wexford County brass Cap on existing 5/8" Iron, stamped PS#39098, 1996 E 1/4 24
- S56°W - 75.55' - 12" Red Pine  
 N30°W - 67.92' - 10" Red Pine  
 N55°E - 51.71' - Fence Post  
 S85°W - 38.55' - Corner fence post

RE-MONUMENTATION  
 MAY 20 1997  
 COMMISSION



Signed by George D. Smith Date 11-21-96  
 Surveyor's Michigan License No. #39098

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983