

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Wexford
(County)

Located In:

Corner Code #

- | | | |
|--------------------------------------|---------------------------|------------|
| 1. Public Land Survey | T <u>21N</u> R <u>10W</u> | <u>M-9</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

RECEIVED

1996 DEC 13 PM 3:34

Linda Loughmiller
 WEXFORD COUNTY, MI
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, George D. Smith, in a field survey on August 13, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K
2	6	5	4	3	2					
3										
4	7	8	9	10	11					
6										
6	18	17	15	15	14					
7										
8	19	20	21	22	23					
9										
10	30	29	28	27	26					
11										
12	31	32	33	34	35					
13										

A. Description of original monument and accessories and/or subsequent restoration:

- M-9) 1837 GLO Quarter Section Post by John Brink, Deputy Surveyor, Hemlock 11 S 17 1/2° W 30, Hemlock 10 N 55° W 15
 1888 A.J. Teed Survey, Liber 1, Page 33, found good stake, stone and both witnesses, Hemlock 18 N 30° W 44L.
 1891 A. J. Teed Survey, Liber 1, Page 32, Corner found no description given, Hemlock S 58 1/2° W 46 1/2
 1969 WCRC Witnesses, Mon. box, no description or witnesses given
 1973 Wilcox Associates LCRC by J. Erickson RLS #16929, Liber 1, Page 514 found 1/2" iron in mon. box at road intersections North-South and East-West. N 45° W 44.05' telephone pole N 40° E 81.48' 8" Red Pine, S 50° E 58.24 9" W. Pine
 1973 Wilcox Associates, Certificate of Survey by J. L. Wilcox RLS #14102 Liber 1, Page 83 found 1/2" iron in mon. box.
 1980 Granger Engineering Certificate of Survey by J. Ray RLS #25869 Liber 1, Page 814, found 3/4" iron in mon. box 10" Pine N 34° E 89.43', 10" Pine N 66° E 84.71' 10" Pine S 54° E 80.03', 10" Pine S 84° W 52.81.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-9) Found 5/8" x 24" Iron in 1" x 12" Galvanized pipe above 3" diameter stone 3' below grade in Mon. box, in Centerline Road to East and 5' East of Centerline Road to South, and in Centerline Road to North. Corner position matches 1888 A.J. Teed's call to centerline Road (819 Teed, 809 Mease) and D. Teed's distance to E 1/4 Section 24 (2634.7' Teed vs 2640.10 m) This corner is accepted as the best available evidence of the position of the original corner being the section corner common to Sections 24 and 25, T21N, R10W and Sections 18 & 19, T21N, R9W

Peer Group Reviewed and Approved

Date: 14 Nov 96
Richard D. Wilcox
 Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-9 Replaced 5/8" x 24" Iron with 5/8" x 36" iron with Wexford County brass cap stamped SE 24, 1996 PS#39098

S46°W - 52.33' - Tw. 8" Cherry
 N33°E - 88.42' - 10" Red Pine
 N66°E - 57.70' - 14" Red Pine (Found Nail)
 S55°E - 80.43' - 14" W. Pine

SURVEYOR'S
 COMMISSION
 2000
 2000



Signed by George D. Smith

Date 11-21-96

Surveyor's Michigan License No. #39098

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983