

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. 21 N. R. 11 W.	B-13, C-13, D-13
2. PROPERTY CONTROLLING IN SECTION.....	T. N. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION.....	T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, CARL F. ROSER, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on JULY 8, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A. Description of original monument and accessories and/or subsequent restoration:~~

B. CONT.

D-13 RE-ESTAB SO. 1/4 COR OF S-32, T21N, R11W, MID-WAY & ON LINE BETW THE SW & SE COR'S OF S-32. APPROX OLD FN COR POSITION (W/OLD FN'S E-W-N, MAY BE CROOKED) IS S77°E, 16'(±5'). FD OLD CED POST W/USFS LOC TAG AT THIS APPROX OLD FN COR POSITION.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- B-13 RE-ESTAB SO. 1/4 COR OF SEC. 31, T21N, R11W, ON LINE BETW THE SE & SW COR'S OF SEC. 31 AND AT PRO-RATED DISTANCE TO U.S. (GLO) SURVEY.
- C-13 RE-ESTAB SEC. COR COMMON TO SEC'S 31 & 32 ON SOUTH LINE OF T21N, R11W, ON LINE & AT PRO-RATED DISTANCE TO SOUR'S SURVEY BETW THE SW COR OF S-31 & THE SE COR OF S-32; THESE BEING FD COR'S THIS SURVEY. SEE E.E. SOURS COMPLETE SURVEY OF S-32(INCL. SO. LINE OF S-31)DATED JUNE 1913; FROM LARGE DARK RED LIBER OF OLD CO. SURVEYOR'S RECORDS, PGS 46 & 47, AT WEXFORD CO. REG OF DEEDS. APPROX. OLD FN. COR (FD OLD CED POST W/WIRE AROUND & FD FN. REMAINS NLY & ELY)12'N & 20'E. FD OLD CED POST W/U.S.F.S. LOC. TAG MARKED SE 31, N65°W, 13'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-13	C-13	D-13
SET STD WEXFORD CO. MON & CED POST.	SET DNR MON & CED POST	SET DNR MON & CED POST
10" ASH N75°E 18.6'	9" R PINE N45°E 22.1'	7" S. MAP N60°E 30.5'
5" W PINE S15°E 10.7'	7" R PINE N75°E 35.8'	13" S. MAP DUE S 2.2'
8" W PINE S70°W 11.1'	2-10" S. MAP S 540°W 38.9'	6" S. MAP S35°W 32.7'
FD OLD FS LOC POST S 5°W 31'		
W/LOC TAG.		
OLD E-W FN REMAINS DUE S 31'		

SIGNED BY Carl F. Roser 03-14-83 DATE

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____



SURVEYOR'S MICHIGAN REGISTRATION NO. _____ WEXFORD COUNTY