

LAND CORNER RECORLATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. 21 N. R. 11 W.		E-13
2. PROPERTY CONTROLLING IN SECTION _____ T. _____ N. S. R. _____ E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ N. S. R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, CARL F. ROSER, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on JULY 8, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

E-13 FD 8" DIA. VIT. TILE & SET 2" X 10" RED PINE HUB W/TACK IN TILE, BURIED FLUSH W/GROUND AT OLD FN COR WITH FENCE REMAINS MOSTLY DOWN N-S-E AND OLD FN WEST THAT IS VISIBLE. THE FD 8" VIT. TILE FITS SOURS DISTANCE WEST ONE MILE (SEE SOURS S-32, 1913 SUR) & SOURS LATER SUR. OF S-33 SAYS "SET SW COR SEC 33 IN 1913 FROM GOV. B.T.'S; RENEWED WITH 8" VIT. TILE".

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-13
FD 8" DIA VIT. TILE & ADDED CED POST
*14" R PINE S78°W 13.03'
*18" ASH N 8°W 16.58'
9" MAPLE S85°E 34.5'

*OLD WITS (FD CABIN SPKS IN TREES)



SIGNED BY Carl F. Roser 03-14-83 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

WEXFORD COUNTY