

APR 16 1999

RECEIVED

1998 DEC 29 AM 10:42

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Linda Loughmiller
WEXFORD COUNTY, MI
REGISTER OF DEEDS

For corners in

WEXFORD (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>21N</u> R <u>11W</u>	<u>I-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, CRAIG J. PULLEN, PS, in a field survey on DECEMBER 18, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4		3		2		1
3													
4	7			8			9		10		11		12
5													
6	18			17			16		15		14		13
7													
8	19			20			21		22		23		24
9													
10	30			29			28		27		26		25
11													
12	31			32			33		34		35		36
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-13 1837 G.L.O. SURVEY BY J. BRINK, WOOD POST, YELLOW PINE 12 N13W 43, BEECH 8 N68E 36

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-13 NO CORNER EVIDENCE OR WITNESSES FOUND. SET 5/8" X 36" IRON AND BRASS CAP BY SINGLE PROPORTIONATE MEASUREMENT BETWEEN THE SW CORNER OF SECTION 34 AND THE SE CORNER OF SECTION 36, T21N, R11W. CORNER FALLS IN PINE PLANTATION AND 300' SOUTH OF TRAIL ROAD. THIS CORNER IS ACCEPTED AS A CAREFUL AND FAITHFUL RE-ESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-13 SECTION CORNER COMMON TO SECTIONS 34 & 35, T21N, R11W
 5/8"X36" IRON & BRASS CAP STAMPED: 34, 35, CJP, 39095, 1998, T21N, R11W

N48°E	8" RED PINE	13.69'
S52°E	9" RED PINE	17.95'
S60°W	9" RED PINE	19.88'
N58°W	10" RED PINE	22.95'

Peer Group Reviewed and Approved
 Date: 4 December 1998
Richard D. Wilcox
 Richard D. Wilcox, Wexford County Surveyor



Signed by Craig J. Pullen Date December 18, 1998

Surveyor's Michigan License No. 39095 FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975
 REVISED JAN., 1983
 REVISED OCT., 1995