

APR 16 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED

1998 DEC 29 AM 10:42

Linda Laughmiller
WEXFORD COUNTY, MI
REGISTER OF DEEDS

For corners in

<u>WEXFORD</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>21N</u> R <u>11W</u>	<u>K-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, CRAIG J. PULLEN, PS, in a field survey on DECEMBER 7, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-13 1837 G.L.O. SURVEY BY J. BRINK, WOOD POST, YELLOW PINE 12 N52 1/2E 25, YELLOW PINE 17 N33 1/2W 45

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-13 NO CORNER EVIDENCE OR WITNESSES FOUND. SET 5/8" X 36" IRON AND BRASS CAP BY SINGLE PROPORTIONATE MEASUREMENT BETWEEN THE SW CORNER OF SECTION 34 AND THE SE CORNER OF SECTION 36, T21N, R11W. THE CORNER IS ON THE TOP OF A HILL AND IN A RED PINE PLANTATION. THIS CORNER IS ACCEPTED AS A CAREFUL AND FAITHFUL RE-ESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13 SECTION CORNER COMMON TO SECTIONS 35 & 36, T21N, R11W
5/8"X36" IRON & BRASS CAP STAMPED: 35, 36, CJP, 39095, 1998, T21N, R11W
N28°E 12" RED PINE 7.07'
S49°E 10" RED PINE 13.72'
S26°W 13" RED PINE 24.90'
N67°W 14" RED PINE 16.64'

Peer Group Reviewed and Approved
Date: 7 December 1998
Richard D. Wilcox
Richard D. Wilcox, Wexford County Surveyor



Signed by Craig J. Pullen Date December 18, 1998

Surveyor's Michigan License No. 39095 FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971