

RECEIVED

JAN 17 1996 LAND CORNER RECORDATION CERTIFICATE 1995 NOV 13 PM 4:27

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in WEXFORD

COMMISSION

Linda Luschmiller
WEXFORD COUNTY, MI
REGISTER OF DEEDS

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>21N</u> R <u>11W</u>	M-4
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, CRAIG J. PULLEN, in a field survey on OCTOBER 5, 1995

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M-4 1837 ORIGINAL G.L.O. SURVEY BY J. BRINK WOOD POST BEECH 12 S62W 44 BEECH 8 N34W 8
- 1902 D.E. TEED SURVEY IN SEC.7, T21N, R10W FOUND STAKE IN ROAD. DON'T KNOW WHO SET IT, BUT IT SEEMED TO COME AT ABOUT THE SAME DISTANCE FROM THE SEC. COR. AS ON SEC.18 W.PINE 30 N44W 119 SW COR WELL N51½E 38
- 1914 FARGO ENGINEERING CO. FOUND IRON PIPE IN CENTER OF ROAD. NO WITNESSES GIVEN
- 1980 USFS SURVEY IN SEC.12 BY P. LEEMON, PS #31595 SECTION BREAKDOWN SHEET SHOWS E¼ CORNER POSITION AT SINGLE PROPORTIONATE MEASUREMENT. RESEARCH OF USFS RECORDS DID NOT SHOW ANY CORNER BEING SET AT THIS LOCATION.
- 1988 & 1994 WILCOX & ASSOC. SURVEYS L.67, P.331 AND L.74, P.102 BY D. SCHRIPEMA, PS#24617 AND J.D. GEERS, PS #33977 RESPECTIVELY. SET ½" IRON & CAP BY SINGLE PROPORTIONATE MEASUREMENT. THIS MEASUREMENT MATCHES CLOSELY TO 1980 SECTION INFORMATION FROM USFS. N84°W 51.54' 8" J.PINE N46°E 59.09' 8" R.PINE N52°W 43.27' P.POLE S46°E 39.25' COR. FE. POST

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-4 FOUND ½" IRON AND CAP IN CENTERLINE 25 ROAD AND 3' SOUTH OF CENTERLINE EAST 40½ RD. AND 3 PREVIOUS WITNESSES. REPLACED ½" IRON WITH 5/8" X 36" IRON AND BRASS CAP. THIS MONUMENT IS ACCEPTED AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.


Peer Group Reviewed and Approved

Date: 10 Nov 95

Richard D. Wilcox
Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-4 ¼ CORNER COMMON TO SECTION 12, T21N, R11W AND SECTION 7, T21N, R10W
- 5/8" X 36" IRON AND BRASS CAP STAMPED:
- CJP, 39095, ¼, 12, 7, 1995
- N46°E 8" RED PINE 59.09'
- N52°W POWER POLE 43.27'
- N84°W 8" JACK PINE 51.64'
- S12°E 6" SCOTCH PINE 113.30'



Signed by Craig J. Pullen Date NOVEMBER 9, 1995
Surveyor's Michigan License No. 39095