

APR 18 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED

1998 DEC 30 PM 2:55

Linda Lougheed Miller  
WEXFORD COUNTY, MI  
REGISTER OF DEEDS

For corners in

WEXFORD  
(County)

Located In:

Corner Code #

1. Public Land Survey

T 21N R 11W M-13

T R Common to:

2. Property Controlling in Section

S T R A-13 T 21N, R 10W

3. Miscellaneous Property in Sec.

S T R M-1 (Lake)  
S T R A-1 (Osceola)

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

I, CRAIG J. PULLEN, PS, in a field survey on NOVEMBER 23, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2			1
3													
4		7		8		9		10		11			12
5													
6		18		17		16		15		14			13
7													
8		19		20		21		22		23			24
9													
10		30		29		28		27		26			25
11													
12		31		32		33		34		35			36
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-13 1837 G.L.O. SURVEY BY J. BRINK WOOD POST CEDAR 10 N15E 19 CEDAR 8 N43 1/2 W 11  
1990 USFS SURVEY ALONG THE TOWNSHIP LINE BY P. LEEMON, PS #31595, L.C.R.C. LIBER 4, PAGE 58, FOUND BOTH GLO CEDAR STUMPS AND REMAINS OF BADLY DETERIORATED CEDAR POST. SET 2"X60" IRON PIPE FILLED W/CONCRETE W/BRASS CAP. TAMARACK 10 N30E 36.30', TAMARACK 5 S63E 72.72', TAMARACK 4 S47W 21.22', TAMARACK 4 N33W 10.81', FIBERGLASS POST SOUTH 1.2'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-13 FOUND 2"X60" CONCRETE FILLED PIPE AND BRASS CAP AND ALL 5 LEEMON WITNESSES. DISTANCE TO THE SOUTH 1/4 OF SECTION 31, T21N, R10W IS 2766.34' (2772'-GLO). DISTANCE TO THE NE CORNER OF SECTION 36, T21N, R11W IS 5232.59'. THIS CORNER IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-13 SECTION CORNER COMMON TO SECTION 36, T21N, R11W, SECTION 36, & T21N, R10W, SECTION 31  
2" X 60" CONCRETE FILLED PIPE & BRASS CAP STAMPED: T21N, R11W, R10W, S36, S31, 1990, PRL, LLS, 31595  
N30°E 10" TAMARACK 36.60' (LEEMON)  
S63°E 6" TAMARACK 72.72' (LEEMON)  
S47°W 6" TAMARACK 21.22' (LEEMON)  
N33°W 6" TAMARACK 10.81' (LEEMON)  
SOUTH FIBERGLASS POST 1.22' (LEEMON)

Peer Group Reviewed and Approved

Date: 6 December 1998  
Richard D. Wilcox  
Richard D. Wilcox, Wexford County Surveyor



Signed by Craig J. Pullen

Date December 6, 1998

Surveyor's Michigan License No. 39095

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975

REVISED JAN., 1983

REVISED OCT., 1995