

MAR 3 1 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1993 DEC -2 PM 3: 50

RECEIVED

For corners in
WEXFORD

(County)

Located In:

Corner Code #

Linda Loughmiller
WEXFORD COUNTY, MI
REGISTER OF DEEDS

1. Public Land Survey	T	21N	R	12W	D-13
	T	21N	R	12W	E-13 ✓
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, CRAIG J. PULLEN, in a field survey on OCTOBER 18, 1993

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- D-13 1837 GLO SURVEY, J. BRINK, WOOD POST DO. 4 N75°W 32 LKS
1973 SURVEY BY J. WILCOX PS #14102, CORNER RECORDED IN L.1, P.274, SET 1/2" IRON ON LINE BETWEEN SE AND SW CORNERS OF SECTION 32, T21N, R12W, N20°W 51.90' 8" OAK S40°W 65.05' 10" OAK S40°E 86.05' 10" OAK
- E-13 1837 GLO SURVEY J. BRINK, WOOD POST, PITCH PINE N50 1/2°E 232 LKS Y. PINE 14" S89°W 543 LKS
1968 SURVEY G. BLASS PS #5489, 8" OAK N40°W 81.68' 18" OAK S61°W 121.02' 9" OAK S51°E 69.11'
1973 SURVEY BY J. WILCOX PS#14102, CORNER RECORDED IN L.1, P.270, FOUND 3/4" PIPE AT INTERSECTION E-W DIRT ROAD AND TRAIL TO NORTH S60°E 69.01' 8" OAK (OLD BLAZE) S35°W 49.58' 6" J. PINE N50°W 81.67' 6" OAK (OLD BLAZE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- D-13 FOUND 1/2" IRON AND 2 WITNESSES FROM L.1, P.274, INTACT. REPLACED WITH 5/8" X 36" IRON WITH BRASS CAP. THIS CORNER IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.
- E-13 FOUND 3/4" PIPE IN CENTERLINE OF ROAD AND 1 WITNESS FROM L.1, P.270, INTACT. REPLACED WITH 5/8" X 36" IRON WITH BRASS CAP. THIS CORNER IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.



Peer Group Reviewed and Approved
Date: Nov. 29, 1993
Richard D. Wilcox
Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13 S 1/4 CORNER, SECTION 32, T21N, R12W SET 5/8" X 36" IRON WITH WEXFORD CO. BRASS CAP STAMPED: S1/4, 32, PS 39095, 1993	E-13 SE CORNER, SECTION 32, T21N, R12W SET 5/8" X 36" IRON WITH WEXFORD CO. BRASS CAP STAMPED: SC, 32, 33, PS 39095, 1993
N19°W 14" BLACK OAK 56.10'	N48°W 8" WHITE OAK 81.67'
S36°W 16" BLACK OAK 65.52'	N35°E 8" WHITE OAK 92.94'
S38°E 16" BLACK OAK 85.95'	SOUTH 6" X 6" CEDAR I.D. POST 15.05'
N65°E 8" JACK PINE 69.85'	N71°W 12" TWIN BLACK OAK 75.88'
SOUTH CENTERLINE ROAD 2.0'	

Signed by Craig J. Pullen 39095

NOVEMBER 23, 1993

Date _____

Surveyor's Michigan License No. _____