

APR 16 1999

RECEIVED

1998 DEC 30 AM 10:19

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Linda Loughmiller
WEXFORD COUNTY, MI
REGISTER OF DEEDS

For corners in

<u>WEXFORD</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>21N</u> R <u>12W</u>	<u>F-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, CRAIG J. PULLEN, in a field survey on OCTOBER, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

F-13 1838 G.L.O. SURVEY BY J. BRINK, WOOD POST PITCH PINE 8 S8 1/2W 688 AND NO OTHER NEAR

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-13 THE SOUTH LINE OF SECTION 33, T21N, R12W, MEASURES LONG AT 5380.70'. SEARCHED AT THE MIDWAY POINT AND FOUND NOTHING. 84' WEST OF SPLIT FOUND BUT DID NOT ACCEPT A RAILROAD SPIKE AT 2606.52' FROM THE SW CORNER OF THE SECTION. ALSO FOUND A USFS WITNESS TAG (SHIELD STYLE) IN A 32" OAK ON THE SOUTH SIDE OF THE ROAD WITH THE BEARING AND DISTANCE STAMPED BUT NO DATE OR INITIALS. THE POSITION OF THE WITNESS FALLS IN THE CENTER OF 52 ROAD AND 2640.1' EAST OF THE SW CORNER OF SECTION 33. USFS SURVEYOR MIKE LANGE RESEARCHED HIS RECORDS FOR THE TAG AND ANY CORNER INFORMATION. NONE WAS FOUND. MIKE FELT THAT LITTLE WEIGHT SHOULD BE PUT ON THE TAG AS EVIDENCE. HE WAS AGREEABLE TO A SINGLE PROPORTIONATE RE-ESTABLISHMENT OF THE CORNER. SET 5/8" X 36" IRON & BRASS CAP ON LINE BETWEEN SW CORNER AND SE CORNER OF SECTION 33, T21N, R12W. THIS CORNER IS ACCEPTED AS A CAREFUL AND FAITHFUL RE-ESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-13 SOUTH 1/4 CORNER OF SECTION 33 T21N, R12W
5/8" X 36" IRON WITH BRASS CAP STAMPED: CJP, 39095, 1998, 33, 1/4
N64°W 12" OAK 65.90'
N28°E 8" OAK 70.70'
S42°E 14" OAK 72.53'
S35°W 32" OAK 41.58'

Peer Group Reviewed and Approved
Date: 9 Dec 98
Richard D. Wilcox
Richard D. Wilcox, Wexford County Surveyor



Signed by Craig J. Pullen Date December 3, 1998

Surveyor's Michigan License No. 39095