

SURVEY & RECONSTRUCTION

RECEIVED

MAR 31 1994

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

1993 DEC 29 AM 10: 33

For corners in

WEXFORD

COMMISSION

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 21N R 12W H-13  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

*Linda Loughmiller*  
WEXFORD COUNTY, MI  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, CRAIG J. PULLEN, in a field survey on DECEMBER 21, 19 93

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- H-13 1837 GLO SURVEY BY J. BRINK, WOOD POST BEECH 10" N33°W 13 LKS HEMLOCK 13 N63°E 10 LKS
- 1909 D.E. TEED SURVEY, BIRCH 10" S18°E 24.3' BIRCH 14" N44½°W 12.3'
- 1968 G. BLASS, PS# 5489 SURVEY, SURVEY IRON WHITE OAK 10" N26°W 26.51' POPLAR 6" S46°W 12.93' POPLAR 12" S25°E 14.06'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- H-13 FOUND BLASS "T" IRON (TYPICAL) AND HIS WITNESSES INTACT. 6" POPLAR IS NOW DEAD. SET 5/8" X 36" IRON WITH BRASS CAP AND LEFT "T" IRON ADJACENT TO IT. THIS CORNER IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.


Peer Group Reviewed and Approved

Date: December 28, 1993

*Richard D. Wilcox*  
Richard D. Wilcox, Wexford County Surveyor

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- H-13 S¼ CORNER, SECTION 34, T21N, R12W
- 5/8" X 36" IRON WITH BRASS CAP STAMPED:
- S¼ 34, 1993, CJP 39095
- S27°E 16" POPLAR 14.09'
- S46°W 6" POPLAR STUMP 12.93'
- N26°W 14" WHITE OAK 26.56'
- EAST 12" MAPLE 59.83'
- N70°W 6" TWIN MAPLE 37.65'



Signed by Craig J. Pullen

Date DECEMBER 28, 1993

Surveyor's Michigan License No. 39095