

APR 16 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED

1998 DEC 30 AM 10:18

Linda Loughmiller
WEXFORD COUNTY, MI
REGISTER OF DEEDS

SECTION

For corners in

<u>WEXFORD</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>21N</u> R <u>12W</u>	<u>I-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, CRAIG J. PULLEN, PS, in a field survey on OCTOBER 13, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-13 1838 G.L.O. SURVEY BY J. BRINK, WOOD POST, BEECH 11 N15E 50, BEECH 11 N77W 30
1909 D.E. TEED SURVEY IN SECTION 34, T21N, R12W, BEECH 18 S27 1/2W 25.6, SUGAR 16 S78 1/2W 39.5
1968 G. BLASS, PS #5489 SURVEY IN SECTION 34, T21N, R12W, AND USFS CORNER CARD BY G. BLASS.
SURVEY IRON, EVIDENCE GOOD. MAPLE 8" S53°E 41.10', MAPLE 4" N41°W 40.40', CHERRY 10" S43°W 13.81'. DISTANCE TO SOUTH 1/4 CORNER OF SECTION 34 IS 2616.02'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-13 FOUND "T" IRON & CAP BY BLASS AND 2 BLASS WITNESSES. SET 5/8" X 36" IRON & BRASS CAP IN PLACE OF "T" IRON. DROVE "T" IRON IN BESIDE IRON. THIS CORNER IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-13 SECTION CORNER COMMON TO SECTIONS 34 & 35, T21N, R12W
5/8" X 36" IRON & BRASS CAP STAMPED: CJP, 39095, 1998, 34, 35, 2, 3
N61°E 4" MAPLE 24.50'
S56°E 12" MAPLE 41.10'
S6°W 6" ASH 9.86'
N43°W 7" TWIN MAPLE 40.40'

Peer Group Reviewed and Approved
Date 30 Oct 98
Richard D. Wilcox
Richard D. Wilcox, Wexford County Surveyor



Signed by *Craig J. Pullen* Date NOVEMBER 6, 1998
Surveyor's Michigan License No. 39095