

SURVEY & REMONUMENTATION

FEB 11 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION
For corners in

<u>Wexford</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>21</u> NR <u>12</u> W	<u>M-2</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

RECEIVED

1997 DEC 11 AM 9:30

Linda Loughmiller
WEXFORD COUNTY, MI
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, George D. Smith, in a field survey on 8-25, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- M-2) 1837 G.L.O 1/4 Section Post by John Brink, Deputy Surveyor; Beech 11 S25°W-61; Beech 7-N69°W-32
- M-2) 1910 D. E. Teed Survey, Liber 1, Page 91, Corner found no desc. given, Sugar 18 S78°E 38 1/4, Sugar 14 S16°E 15 1/4

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Re-set corner by single proportion between found Northeast corner and found Southeast corner. Distance agrees with D.E. Teed's distance to North closely 2645.14, 2648.5 Teed. This corner is accepted as a careful and faithful re-establishment of the position of the original corner being the 1/4 corner common to Section 1, T21N, R12W and Section 6, T21N-R11W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" iron with Wexford County brass cap stamped E 1/4 1, 1997, 39098

- S15°W 21.18' 8" Ash
- S50°E 15.53' 7" Beech
- N80°E 1.63' 7" Maple
- N70°W 9.76' 4" Maple

Peer Group Reviewed and Approved

Date: 10-30-97
Richard D. Wilcox
Richard D. Wilcox, Wexford County Surveyor

Signed by *George D. Smith*
Surveyor's Michigan License No. _____

Date 10-30-97

