

SURVEY & REMONUMENTATION

FEB 11 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED

1997 DEC 11 AM 9:30

Linda Loughmiller
WEXFORD COUNTY, MI
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in

Wexford

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|-----------------------------|-------|
| 1. Public Land Survey | T <u>21</u> N R <u>12</u> W | M-4 |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, George Smith, in a field survey on 8-25, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- M-4) 1837 GLO 1/4 Section Post by John Brink, Deputy Surveyor; Beech 8 S20°W34; Sugar 12 N67°W19
- 1914 Fargo Engineering Co. Survey. No U.S. evidence found, set 1" bolt 30" long with not on each end Hemlock stump 36" N22E, 0.38 feet, Maple 6" S37W 1.00 feet, Hemlock stump 20" N80E 0.23½ feet.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Did not find Fargo iron or witnesses, area has been built up due to construction of 13 Road, 1954 Wexford County Road plans did not show corner. Reset corner by single proportionate measure between the NE corner of Section 12 and the SE corner of Section 12. Corner falls 13.5 feet E'y of centerline road North-South 13 feet ± S'y of treeline to East and 39 feet N'y of O.H.P.L. crossing. This corner is accepted as a careful and faithful re-establishment of the position of the original corner being the quarter corner common to Section 12, T21N, R12W and Section 7, T21N, R11W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8"x36" iron with Wexford County brass cap stamped
PS: 39098, E¼ 12, 1997
N70°E 47.76 feet 16" Red Pine
N35°E 65.15 feet 6" Basswood
N50°W 54.58 feet 18" Apple
S65°W 92.20 feet E'y Nut (Head high) on S'y Power Line Tower

Peer Group Reviewed and Approved

Date: 30 Oct 97
Richard D. Wilcox
Richard D. Wilcox, Wexford County Surveyor

Signed by George Smith
Surveyor's Michigan License No. 39098

Date 10-30-97

