

SURVEY & REMONUMENTATION

FEB 11 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Wexford
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|-----------------------------|-------|
| 1. Public Land Survey | T <u>21</u> N R <u>12</u> W | M-10 |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

RECEIVED

1997 DEC 11 AM 9:31

Linda Longmiller
WEXFORD COUNTY, MI
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, George Smith, in a field survey on July 3, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- M-10) 1837 GLO Quarter Section Post by John Brink, Deputy Surveyor; Aspen 7, S28½° W10, W. Pine N75½°W 15
- 1889 A.J. Teed Survey, Liber 1, Page 103, corner found no description given, W. pine 11, S85°E 39'
- 1974 J. Granger PS #16041 Set corner by single proportionate measure between found corners 1/2 mile to North and South, no witnesses or description of corner given.
- 1990 Phillip Case PS #30079, Certificate of Survey, Liber 69, Page 597, Found Wexford County Mon. East USFS Post 44.15', N08°E 6" J. Pine 50.25', N68°E 10" T.W. Cherry 88.90', S10°E 4" J. Pine 39.15'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Wexford Co. mon. with aluminum cap ±30' Wly North-South 2 trk. and 3 witnesses from 1990 Case PS #30079 certificate of survey. This corner is accepted as a careful and faithful re-establishment of the position of the original corner being the quarter corner common to Section 25, T21N-R12W and Section 30, T21N-R11W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Wexford County Mon. with Aluminum cap
N72°E 88.49' Found nail in 18" Tw. Cherry
N10°E 50.23' Found nail in 8" J. Pine
S05°E 39.12' Found nail in 5" J. Pine
N51°W 48.37' Set nail in 4" cherry

Peer Group Reviewed and Approved

Date: 30 Oct 97
Richard D. Wilcox
Richard D. Wilcox, Wexford County Surveyor

Signed by _____
Surveyor's Michigan License No. 39098

Date 10-30-97

