

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. <sup>22</sup>~~22~~ NR. <sup>9W</sup>~~8W~~ . . .

Wexford - Missaukee COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 13, 24, 18, 19

DESCRIPTION OF CORNER MONUMENT 1" pipe, with 4" brass cap

WITNESSES TO CORNER

7" W. Birch - N40W - 65½ links

9" Poplar - S62W - 54½ links

18" Diam. Boulder N20W - 30 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a partial resurvey of this township. Found a very old post at corner, with NE and SE probable government BT stumps in place. Corner checks acceptably with swamp edge in all directions. Found another old stake point when setting corner.

Corner placed and witnessed April 28, 1958.

SURVEYORS SEAL

SIGNED *Kenneth J. Dettling* . . . DATE *6/2/58*  
REGISTERED LAND SURVEYOR