

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

WEXFORD COUNTY


T 22 N R 9 W

DESCRIPTION OF CORNER Sec. corner common to Sections 14-15-22-23

CORNER MONUMENT Found Std Dept Mon. Set Cedar Guard Post

DATE MONUMENT PLACED AND WITNESSED 4-27-71

WITNESSES TO CORNER..... 5" Maple N 30 W 15.0'



12" Oak S 64 E 6.6'

18" Oak S 53 W 15.2'

AND

28" Oak S 13 W 8.9'

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was recovered and monumented by Dept. Surveyor, Ken Ostling, in 1959. He found definite evidence (shredded wood & discoloration) of Govt. Post at corner. Also stumps for both USBTs in place. Corner falls directly in line with old Page wire fence to South.

SURVEYOR'S SEAL

SIGNED

Carl F. Power
REGISTERED LAND SURVEYOR

DATE

5-4-71

DISTRIBUTION:

12028

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68