

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 22. NR. 9. W. . .

Wexford COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 14-15-22-23

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 5" Maple - N34W - 22½ links

10" R. Oak - S66E - 10 links

* 14" R. Oak - S51W - 22½ links

* Marked for previous NBT

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a partial resurvey of this township. Found definite evidence (shredded wood and discoloration) of government post at corner. Stumps for both government BTs in place. Falls directly in line with old page wire fence south. A square stake, set within last 5 years, here also, faced by several blazed trees.

Corner was set and witnessed April 16, 1959.

SURVEYORS SEAL

SIGNED

Herbert J. Ostling
REGISTERED LAND SURVEYOR

DATE 4/17/59