

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 22 NR. 9 W.

Wexford COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 14 and 23

DESCRIPTION OF CORNER MONUMENT 1" x 24" pipe below surface

WITNESSES TO CORNER

6" Maple	-	S46E	-	41 links
12" R. Oak	-	S38W	-	36½ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a partial resurvey of this township. Corner was restored from probable government BT stumps, only ones in vicinity that can be found to fit the calls of the government record. Corner falls in trail on old RR grade, within 5 links of position for proportion corner. Could find no evidence of post due to grade construction. Checks for distance and line between good corners east and west.

Corner was placed and witnessed April 16, 1959.

SURVEYORS SEAL

SIGNED

Kenneth J. Otting
REGISTERED LAND SURVEYOR

DATE 4/17/59