

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD

WEXFORD COUNTY


T 22 R 9 W

DESCRIPTION OF CORNER Sec. corner common to Sections 13-14-23-24

CORNER MONUMENT Found Standard Dept. Mon. Set Cedar Guard Post

DATE MONUMENT PLACED AND WITNESSED 4-27-71

WITNESSES TO CORNER..... 9" Oak N 20 W 32.9'



18" Oak S 71 W 11.8'

8" Maple S 2 E 41.1'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was recovered and monumented by Dept. Surveyor, Ken Ostling, in 1959. He found a 3/4" pipe at corner with stumps in place for both USBTs. He also found a very old pointed stake bottom when setting the Dept. Mon., which likely had been set by Teed when restoring the Govt. corner some 40-50 years ago.

SURVEYOR'S SEAL

SIGNED

*Carl F. Boer*  
REGISTERED LAND SURVEYOR

DATE

5-4-71

DISTRIBUTION:

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

12028

R 4047  
Rev. 10/68