

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 22 NR. 9 W.

Wexford

COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 23 and 24

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

24" Oak - N40E - 135 links

10" Maple - S39E - 156 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a partial resurvey of this township. Found 3/4" pipe at corner with evidence of older stake point below. Holes for sites of both probable government BTs. Distance checks good with stream crossing north. Corner is 9 links out of line with Section corners, but this is not unreasonable or unusual. Falls at NE corner of pine plantation.

Corner was set and witnessed April 16, 1959.

SURVEYORS SEAL

SIGNED

Kenneth J. Ostling
REGISTERED LAND SURVEYOR

DATE 4/17/59