

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 22.. NR. 9 W..

..... Wexford..... COUNTY

DESCRIPTION OF CORNER ..... 1/4 corner at center of Section 10 .....

DESCRIPTION OF CORNER MONUMENT .. 1" x 24" pipe .....

WITNESSES TO CORNER ..... 22" Maple ..... N 68 1/2 W ..... 124 links

..... 24" W. Pine Stump ..... N 81 E ..... 157 1/2 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by survey procedure for the subdivision of sections by Forestry Division survey crew while making a partial resurvey of this township. Set the corner at the true intersection of the 1/4 lines by running lines between the opposite 1/4 corners. The W 1/4 corner of Section 10 was not established but the midpoint between section corners was assumed for the purpose of this subdivision. The meandering alignment of the fences seemed to eliminate them from consideration as to the location of the 1/4 line or corner.

Corner was placed and witnessed September 23, 1958.

SURVEYORS SEAL

SIGNED

*Kenneth J. Osting*  
REGISTERED LAND SURVEYOR

DATE 9/26/58