

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. <sup>22</sup>22 NR. <sup>8W</sup>9W

Wexford - Missaukee COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 18 & 13

DESCRIPTION OF CORNER MONUMENT 1" pipe, with 4" brass cap - 4" below surface

WITNESSES TO CORNER

9" W. Oak - N85W - 42 links

10" R. Oak - S61E - 39 1/2 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by Forestry Division survey crew while making a partial resurvey of T22N R9W. Could find no evidence of a corner, the government BT's apparently having been removed in road construction. Set corner by proportionate measure between section corners. Falls on west edge of present dirt road.

Corner placed and witnessed May 2, 1958.

SURVEYORS SEAL

SIGNED *Kenneth J. Oetting* DATE *6/2/58*  
REGISTERED LAND SURVEYOR