

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


WEXFORD COUNTY
T 22 N R 9 W

DESCRIPTION OF CORNER 1/4 corner common to Sections 22 - 23
CORNER MONUMENT Set Std. Dept. Mon. & Cedar Guard Post in remains of old
DATE MONUMENT PLACED AND WITNESSED N-S fence.
4-20-71

WITNESSES TO CORNER.....

18" Twin Oak	N 21 E	184.7'
28" Oak	N 49 W	168.8'

AND



CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was reestablished equidistant between Sec. corners to N & S, and in line with old N & S fence remains. The longitudinal position of the corner by the old fence is very close to being on a straight line between Section corners. The corner was restored while making a retracement survey in this area.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Carl F. Reser
REGISTERED LAND SURVEYOR

DATE

4-27-71

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

12028

R 4047
Rev. 10/68