


STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD

WEXFORD COUNTY  
T 22 R 9 W

DESCRIPTION OF CORNER 1/4 corner common to Sections 23-24  
CORNER MONUMENT Reset Dept. Mon. (1"x48" pipe with brass cap) and Cedar Guard post  
along side of old 3/4"x36" pipe.  
DATE MONUMENT PLACED AND WITNESSED 4-19-71

WITNESSES TO CORNER..... 9" Twin Maple N 14 W 49.4'



24" Oak N 42 E 89.1'

18" Tri-Maple S 37 E 103.5'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Restored Dept. Mon. along side of old 3/4"x36" pipe. Dept. Mon was originally set along side of 3/4" pipe by Dept. Surveyor, Ken Ostling, in 1959. Mon. was removed by Power Company during clearing for power line. We were able to recover the pipe from Ostling's witnesses.

SURVEYOR'S SEAL

SIGNED

*Carl F. Bauer*  
REGISTERED LAND SURVEYOR

DATE

4-27-71

DISTRIBUTION:

12028

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68