


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

WEXFORD & MISSAUKEE COUNTY
T 22 N R 6 6 9 W

DESCRIPTION OF CORNER 1/4 corner common to Sections 24 & 19
CORNER MONUMENT Set Std. Dept. Mon. and Cedar Guard Post
DATE MONUMENT PLACED AND WITNESSED 4-20-71
WITNESSES TO CORNER..... 24" Oak N 32 W 100.5'



14" Oak S 89 W 95.1'
18" Oak N 12 E 16.1'
AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established while making a retracement survey in this area. The corner was set equidistant and on line between Sec. corners to N & S. A map showing the West Section line of Sec. 19, T22N-R6W was obtained from Forace Smith. He advised me that he had hired Matt McClung, RLS, Marion to run the West line of Sec. 19 and that McClung had prepared the map. Apparently, McClung set a wood picket for the West 1/4 corner of Sec. 19, and the map shows an identical procedure for setting the 1/4 corner as we used. We did find a possible wood picket at our position for the 1/4 corner.

Note: Our N-S random line is 28' West of the 1/4 corner. McClung's Rand, according to the map, would have been about 26' West of his 1/4 corner.

SURVEYOR'S SEAL

SIGNED Carl F. Roser DATE 4-27-71
REGISTERED LAND SURVEYOR 12028

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing