


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

WEXFORD COUNTY
T 22 N R 9 W

DESCRIPTION OF CORNER Ctr 1/4 corner Section 27
CORNER MONUMENT Found rotten 3/4" pipe. Added 1"x36" pipe & cedar Guard post w/location tag
DATE MONUMENT PLACED AND WITNESSED 4-30-71
WITNESSES TO CORNER.....



12" R. Pine	S 82 E	57.48'
12" R. Pine	N 51 E	74.77'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner (center of Sec. 27) was recovered while making a retracement survey in this area. We were able to find an old 3/4" pipe almost exactly at the intersection of the N-S & E-W 1/4 lines. Teed surveys in Sec. 27 dated 1885, 1887, 1891 & 1904 indicate that he subdivided Sec. 27 and set the center post at the intersection of the 1/4 lines. It is my opinion that we have definitely recovered Teed's center of Section even though old fences in the area are very misleading.

SURVEYOR'S SEAL

SIGNED Carl F. Rozer DATE 5-6-71
REGISTERED LAND SURVEYOR 12028

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68