

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

22 8W  
T. 22 NR. 9W

Wexford - Missaukee COUNTY

DESCRIPTION OF CORNER Section corner common to Section 7, 18, 12, 13

DESCRIPTION OF CORNER MONUMENT 1" pipe, with 4" brass cap

WITNESSES TO CORNER

5" Elm - S49E - 224 links

7" Aspen - S70W - 165½ links

S. Rail of RR North - 37 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED. This corner was established by Forestry Division survey crew while making a partial resurvey of this township. This corner was established in the center of an ancient township road grade which comes from the south and ends about 50 links north at the RR, at proportionate measurement between the corner of Sections 13 and 24 south and the town corner north. This longitudinal position was chosen over the direct line proportion since it seemed indicated by the measurements west for 2 miles and east to the marsh. Our position makes the south line of Section 12 equal to the south line of Section 11, as intended by the government survey, and each mile 4 links longer than record. The distance east to the marsh edge, although somewhat indefinite relative to its position in 1852, would conform acceptably with the record. It also seemed likely the old grade might have been constructed to an established corner. A direct line proportion would place the corner about 16 links east of our position, by our calculations.

The 3 mile latitudinal proportion seemed justified in the absence of better evidence, since this position places the corner very nearly on line over the corners for 2 miles west, as was the intent of the government survey, and checks favorably with the lake margins north. Although no state land is involved, this corner was set to establish control for the corners west, north and south.

SURVEYORS SEAL Corner placed and witnessed May 2, 1958.

SIGNED *Kenneth J. O'Brien* DATE *6/2/58*  
REGISTERED LAND SURVEYOR