

✓

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. ²²~~23~~ NR. ^{9W}~~9W~~ . . .

----- Wexford ----- COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 1 & 36 -----

DESCRIPTION OF CORNER MONUMENT 1" pipe, with 4" brass cap -----

WITNESSES TO CORNER -----

6" R. Oak - N36E - 16 links -----

6" R. Oak - S38E - 20 links -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement between Section corners by Forestry Division survey crew. Could find no conclusive evidence of the government corner, although a W. Pine stump turn-out is in approximately the right position from our established corner, for the NW government BT.

Corner placed and witnessed April 29, 1958.

SURVEYORS SEAL

SIGNED Kenneth J. Orthuis ----- DATE 6/2/58
REGISTERED LAND SURVEYOR