

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. <sup>22</sup>~~23~~ NR. <sup>9W</sup>~~9W~~ . . .

Wexford COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 4 & 33

DESCRIPTION OF CORNER MONUMENT 1" pipe, with 4" brass cap

WITNESSES TO CORNER

14" Cherry - S67W - 29 links

8" Double Maple N9W - 36 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a partial resurvey of this township. Found old stake point at corner, probably Delmore Teed's, which perpetuated corner as established by A. J. Teed in 1885. Delmore Teed's NBT stumps in place: a W. Pine stump 24 N72E 91, a W. Pine stump 24 S80 $\frac{1}{2}$ W 66, a W. Pine stump 20 N82W 61. Although no state land is involved, the corner was set to perpetuate an old corner, which could control adjacent surveys. It also falls on forest boundary.

Corner was placed and witnessed April 25, 1958.

SURVEYORS SEAL

SIGNED Kenneth J. Oetting DATE 6/2/58  
REGISTERED LAND SURVEYOR