

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 22. NR. 9W.

Wexford COUNTY

DESCRIPTION OF CORNER W 1/8 corner common to Sections 11 & 14

DESCRIPTION OF CORNER MONUMENT 1" x 24" pipe

WITNESSES TO CORNER

28" B. Oak - N26W - 34 links

14" Maple - S70E - 28 1/2 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established at midpoint, on line, between 1/4 corner east and Section Corner west by Forestry Division survey crew. Teed's large W. Pine witness SW pulled out in road construction. In line with old fence roll north, and random fence line south. Set to establish boundary between state and private lands.

Corner placed and witnessed April 23, 1958.

SURVEYORS SEAL

SIGNED

Kenneth J. Oetting
REGISTERED LAND SURVEYOR

DATE 6/2/58