

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

22 8W
22 9W
T...23 NR...8W...
23 9W

Wexford - Missaukee COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 6,1,31,36

DESCRIPTION OF CORNER MONUMENT 1" pipe, with 4" brass cap

WITNESSES TO CORNER 6" Cedar - N12W - 30 links

6" Cedar - N57E - 45½ links

6" Balsam - S43E - 23½ links

5" Cedar - S35W - 37 links

A 14" Tamarack stub, scribed R8W, T23N S31, bears N7E.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a partial resurvey of T22N, R9W. Found an old squared post at corner, and another stake point. Corner was set from the probable NW government BT, which is down and rotting, but has evidence of both faces with the marks plain on lower face. Corner is faced by another BT which appears to be of a later date, yet can be aged between 60 and 80 years old, since it grew for 50 years after it was marked, and is at present in an advanced stage of interior decay having also lost its top. Corner checks good with swamp edges south and east. Distance west to swamp edge appears to have been erroneously recorded since it is but 4.50 chains as against 8.00 chains, government record. Although this corner appears to date back to the era of A. J. Teed, I could find no record of it in Wexford or Missaukee County survey records.

Corner placed and witnessed April 29, 1958.

SURVEYORS SEAL

SIGNED *Kenneth J. Ottling*
REGISTERED LAND SURVEYOR

DATE *6/2/58*