

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 22 NR. 9W.

Wexford COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 10 & 11

DESCRIPTION OF CORNER MONUMENT 1" pipe, with 4" brass cap

WITNESSES TO CORNER

26" Y. Pine stump - S12W - 130 1/2 links

36" W. Pine stump - N20E - 113 1/2 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a partial resurvey of this township. Found a 1/2" x 18" pipe at corner, presumably by M. M. Buck in 1935 which perpetuates the corner as established by Teed in 1901 by proportionate measurement. Remains of Teed's W. Pine 24 N23 1/2 E 33 is in place. Our measurement for the N 1/2 mile checks Buck's within 2 links. 1/4 corner is on line and within 4 links of midpoint, by our measurement. Found remains of very old stake point, as well as Buck's when setting corner.

Corner placed and witnessed April 22, 1958.

SURVEYORS SEAL

SIGNED Kenneth J. Oetting
REGISTERED LAND SURVEYOR

DATE 6/2/58