

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T.22.. NR.. 9W..

Wexford COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 2,3,10,11

DESCRIPTION OF CORNER MONUMENT 1" pipe, with 4" brass cap

WITNESSES TO CORNER

10" Maple - S43W - 28 links

7" Maple - N19W - 95 links

8" W. Birch - N86½E - 51 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a partial resurvey of this township. Found 1/2" x 18" pipe at corner, presumably set by M. M. Buck in 1935. Corner originally established by Dalmore Teed in 1901 from government BT's as recorded in county survey records. Found and used by C. E. Stackus in 1928. Teed's witness stumps, a W. Pine 20 S86W 41, a W. Pine 24 N203/4E 58 are in place. The W. Pine 24 N74½E 42 is gone. Buck's witness stumps as described on his unrecorded plat correspond with those of Teed and Stackus. Checks for record measurement north to lake, but somewhat short east to lake. Point for Bureau of Land Management corner is 78 links north and 2 links east. Found point of old stake when setting corner. Roots of probable government BT SE.

Corner placed and witnessed April 22, 1958.

SURVEYORS SEAL

SIGNED *Kenneth J. Oetting*
REGISTERED LAND SURVEYOR

DATE *6/2/58*