

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. <sup>22</sup>23. NR. <sup>9W</sup>9W...

Wexford COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 1,2,35,36

DESCRIPTION OF CORNER MONUMENT 1" pipe, with 4" brass cap

WITNESSES TO CORNER

8" R. Oak - N14E - 62½ links

8" R. Oak - S32E - 50½ links

9" R. Oak - S46W - 36½ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a partial resurvey of this township. Found a 3/4" pipe at corner, as set and recorded by C. E. Stackus, whose BT's a W. Pine stump 36 S44½W 9 and a W. Pine stump 30 N42E 77 are in place. Check very good with swamp edge south. Distance west to 1/4 corner is 31 links short of record but land is very rolling.

Corner placed and witnessed April 21, 1958.

SURVEYORS SEAL

SIGNED *Kenneth J. O'Brien*  
REGISTERED LAND SURVEYOR

DATE 6/2/58