

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. ²²23. NR. ^{9W}9W

Wexford COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 2 & 35

DESCRIPTION OF CORNER MONUMENT 1" pipe, with 4" brass cap

WITNESSES TO CORNER

14" R. Pine - S60W - 208 links

14" B. Oak - S28E - 53 1/2 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a partial resurvey of this township. Found what I believe to be the government corner as previously located and recorded by Delmore Teed in 1901 and C. E. Stackus in 1927. Found definite stake point at corner, a W. Pine stump 18 N58W 20 and a W. Pine stump 20 S39W 29 1/2 for Teed's BT's. The OBT stump, a Y. Pine 12 N5 1/2 W 28 in place with possible face. Checks good with swamp edge west.

Corner placed and witnessed April 21, 1958.

SURVEYORS SEAL

SIGNED *Kenneth J. Oetting*
REGISTERED LAND SURVEYOR

DATE 6/2/58