

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. ²²23 NR. ^{9W}9W

Wexford COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 2,3,34,35

DESCRIPTION OF CORNER MONUMENT 1" pipe, with 4" brass cap

WITNESSES TO CORNER

12" W. Oak - N13W - 60 links

12" B. Oak - S80W - 19 links

9" R. Pine - S24E - 90 1/2 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a partial resurvey of this township. Found what I believe to be the government corner as located by Delmore Teed in 1901 and used by C. E. Stackus in 1927. Teed's witness stumps a Y. Pine 18 N54W 7 1/2 and a W. Pine 16 N38W 42 are in place. Roots of the government corner tree in place, and remains of SE OBT. Could find no iron as set by Stackus, but it could have been pulled out, since corner is only 6 feet from old wagon road. Corner checks exactly with government chainage north to swamp and good to lake south. Distances E & W along town line are irregular between corners, but should be expected since this is very rolling terrain.

Corner placed and witnessed April 21, 1958.

SURVEYORS SEAL

SIGNED *Kenneth J. Ostberg* DATE *6/2/58*
REGISTERED LAND SURVEYOR