

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

22 8W
T. 22 NR. 9W

Westford - Missaukee COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 6,7,1,12

DESCRIPTION OF CORNER MONUMENT 1" pipe, with 4" brass cap

WITNESSES TO CORNER

6" R. Oak - S75W - 56½ links

20" B. Oak - S44E - 91½ links

16" B. Oak - N46E - 44 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by Forestry Division survey party. Could make no positive identification of government corner so established this corner by proportionate measure between Section corner 1 mile south ~~and Town corner 1 mile south~~ and Town corner 1 mile north. This point conforms very closely with the government record in latitude, and checks for longitude fairly good with a small pond about 30 chains west, considering proportionate measurement.

Corner placed and witnessed May 2, 1958.

SURVEYORS SEAL

SIGNED Kenneth J. Oetting DATE 6/2/58
REGISTERED LAND SURVEYOR