

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 22. NR. 9. W. .

Wexford COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 1 and 2

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

6" R. Oak N 59 W 67½ links

5" R. Oak N86 E 36½ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while on a survey project in this area. Found well-preserved stake point at corner with discoloration indicative of a much older point below. This corner I believe to be the one found and renewed by Teed in 1901, as per his record. Stumps in place for government BTs, and a hole SW for Teed's witness. Checks for distance to swamp edge north, and also Teed's record for distance south to section corner. Falls within one link of a direct line between section corners.

Corner was placed and witnessed June 3, 1958.

SURVEYORS SEAL

SIGNED *Harold J. Oetgen*
REGISTERED LAND SURVEYOR

DATE 6/5/58