

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 22. NR. 9 W. . .

Wexford COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 2 and 11

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

10" R. Oak - N 20 E - 205 links  
Witness corner is N89 $\frac{1}{4}$ W - 178 $\frac{1}{2}$  links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a survey in this area. Found a 4"x4" stake, tipped over and nearly submerged in mud, at position for 1/4 corner. Unable to determine the exact position where stake stood so re-established corner 1.78 $\frac{1}{2}$  ch east of witness corner which was definitely identified. Pond is now nearly dry so corner was set to eliminate confusion between this corner and the witness corner.

Corner was placed and witnessed June 6, 1958.

SURVEYORS SEAL

SIGNED

*Kenneth J. Ostling*  
REGISTERED LAND SURVEYOR

DATE 6/9/58