

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 22. NR. 2 W. . .

Wexford COUNTY

DESCRIPTION OF CORNER Witness corner to 1/4 corner between Sections  
2 and 11

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap, marked  
2 WO

WITNESSES TO CORNER ----- 11 -----

7" W. Oak - N 62 W - 116½ links

6" W. Oak - S 38 W - 117½ links

1/4 corner is S 89½ E - 178½ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a survey in this area. Found Teed's corner as established in 1901 from remains of government BTs. Sites for both government BTs in place and remains of Teed's witness N57W 96 links. Stake point well preserved in water sand and was found by digging. No surface evidence of corner. Corner falls on west edge of presently dry pond, within 4 links of straight line between section corners.

Corner placed and witnessed June 6, 1958.

SURVEYORS SEAL

SIGNED

*Kenneth J. Wetting*  
REGISTERED LAND SURVEYOR

DATE 6/9/58