

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T 22 N R 9 W
T 23 NR 2 W

Wexford COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 3-4-33-34

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 7" B. Oak N 72 W 53½ links

20" R. Pine S 20 W 62 links

18" R. Pine S 48 E 42½ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a partial resurvey of this township. Excavated a very old stake point supported by stumps of government BT's, possibly by D. Teed. Checks fair to swamp edge south and is about 5' SE of position of proportioned corner.

Corner placed and witnessed August 29, 1958.

SURVEYORS SEAL

SIGNED *Kenneth J. Oetting* DATE 9/16/58
REGISTERED LAND SURVEYOR