

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T..22. NR...9 W.

.....Wexford.....COUNTY

DESCRIPTION OF CORNER ... 1/4 corner common to sections 10 and 15

DESCRIPTION OF CORNER MONUMENT Left 1/2" iron bar in place

WITNESSES TO CORNER Notch in root of 26" Elm ... S 66 1/2° W ... 65 Links

Notch in root of 24" Elm ... N 40° W ... 109 3/4 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR
RESTORED.

This corner was found by Forestry Division survey crew while making a partial resurvey of this township. Found a 1/2" iron bar at road intersection, set by unknown surveyor. No means for disproving its authenticity, and it checks lines of occupation, so was accepted and used in this survey. The above references were taken to perpetuate its present location.

Corner was witnessed 9/15/58.

SURVEYORS SEAL

SIGNED *Kenneth J. Ostling*
REGISTERED LAND SURVEYOR

DATE - 9/18/58