

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 22 .. NR. 9. W ..

Wexford COUNTY

DESCRIPTION OF CORNER 1/4 corner common to sections 3 and 10

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 24" B. Oak N 86 W 166 Links

10" Maple N 19 E 155 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a partial resurvey of this township. Found evidence of old stake point supported by stumps SW and SE for Teed's witnesses of 1901, and large hole NE for government BT. Makes east $\frac{1}{2}$ mile between 3 and 10 13 links longer than Teed's record, which is consistent with other comparisons.

Corner placed and witnessed 9/15/58.

SURVEYORS SEAL

SIGNED Kenneth J. Ostling DATE 9/18/58
REGISTERED LAND SURVEYOR