

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T..22. NR..9W..

-----Wexford-----COUNTY

DESCRIPTION OF CORNER .. Section corner common to sections 5-6-7-8 ..

DESCRIPTION OF CORNER MONUMENT .. 1" pipe with 4" brass cap ..

WITNESSES TO CORNER .. 20 " R. Pine Stump .. S 33 E .. 53 $\frac{1}{2}$  Links

.. 8" R. Oak .. N 45 W .. 191 $\frac{1}{2}$  Links.

.. 5" Maple .. S 57 W .. 175 Links.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR  
RESTORED.

This corner was found by Forestry Division survey crew while making a partial resurvey of this township. Found very good evidence of stake point at corner. Remains of both government BT stumps in place N W and SE. Corner is supported by government  $\frac{1}{4}$  corner and section corner east.

Corner placed and witnessed 9/16/58.

SURVEYORS SEAL

SIGNED Kenneth J. Otting DATE 9/18/58  
REGISTERED LAND SURVEYOR