

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T.22.. NR.. 9.W..

----- Wexford ----- COUNTY

DESCRIPTION OF CORNER .. 1/4 corner common to Sections 7 and 8.

DESCRIPTION OF CORNER MONUMENT .. 1" pipe with 4" brass cap

WITNESSES TO CORNER .. 6" Maple .. S 80 E .. 54 links

.. 10" Maple .. S 1 W .. 70 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR
RESTORED.

This corner was established by proportionate measurement between section corners by Forestry Division survey crew while making a partial resurvey of this township. Could not identify the government Hemlock and Beech, so considered proportionate measurement the only means of restoration. Corner is faced by W. Pine stump that appears to have been faced for witness long ago, but could find no record of it in county files.

Corner placed and witnessed September 29, 1958.

SURVEYORS SEAL

SIGNED *Kenneth J. Ostery* .. DATE 9/30/58
REGISTERED LAND SURVEYOR