

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T.22.. NR..9.W..

----- Wexford ----- COUNTY

DESCRIPTION OF CORNER .. 1/4 corner common to Sections 7 and 18 ..

DESCRIPTION OF CORNER MONUMENT. Left 4" x 5" x 18" stone in place, surrounded by broken glass and crockery.

WITNESSES TO CORNER .. 24" W. Pine Stump .. N 29 E .. 26 links

.. Corner fence post .. S 2 W .. 50 1/2 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a partial resurvey of this township. Found a large stone, described above, surrounded by glass and crockery in place. Probably De Voe's corner of record in 1908. A large pine stump in place for his NBT of record. Corner has been occupied to by fencing, and since no identification of the government BTs could be made, was accepted as valid in this survey.

Corner was placed and witnessed September 29, 1958.

SURVEYORS SEAL

SIGNED *Renneth J. Ostling* DATE 10/1/58
REGISTERED LAND SURVEYOR